

Homestead Implements Pinnacle Series Land Plane Technical Specification			
Working Width	60" (1.52 m)	72" (1.83 m)	84"(2.13m)
Overall Width	65 1/2" (1.66 m)	77 1/2" (1.97 m)	89 1/2" (2.27 m)
Number of Scarifier Shanks	5	6	7
Maximum H.P. Rating	56 Horsepower		
Total Weight with Shanks	424 lbs. (193 kg)	497 lbs. (226 kg)	549 lbs. (250 kg)
Overall Length	52 " (1.30 m)		
Overall Height	36 1/2" (90.2 cm)		
Side Panel Height	15 1/4" (36.2 cm)		
Side Panel Length	44" (1.12 m)		
Side Panel Thickness	1/4" (25.4mm) thick side panels with replaceable skid shoe underneath.		
Front Main Beam & Scarifier Support	4" x 3" x 3/16" (10.2cm x 7.6cmx 4.8mm) Square Tubing with 3/8" x 3" long shank reinforcements		
Skid Shoe Dimensions	1/4" (6.4 mm) Thick x 2" (5.1 cm) wide x 44" (1.12 m) long.		
Scarifier Shank Construction	3/4" x 2.5" x 18" (19 mm x 63 mm x 458 mm) Replaceable heat treated dimpled-on tips		
Cutting Edges	Two High carbon steel, heat treated cutting edges 1/2" x 6" (1.2cm x 15.2cm)		
Cutting Edge Placement	Two parallel cutting edges placed at 5 degree and 17.5" (44.6cm) apart.		
Cutting Edge Adjustment	Continuous height adjustment from skid level to 1-3/4" (4.5 cm) below skid level.		
Shank Adjustments	3 1/4" and 1 1/4" (8.3 cm and 3.2 cm) below skid level 1/4" and 2 1/4" (0.6 cm and 5.7 cm) above skid level		
3-Point Hitch Type	Cat. 1 Quick-Hitch Compatible	patible Category 1 & 2 Quick-Hitch Compatible	